

To

All S.E/OP Circle,
Under DHBVN

MemoNo.Ch-72/D-III-58/Vol-I


Dated:14.08.2018

Subject- Approved revised rate list for Supply & Erection of the items/material for estimation purpose of preventive maintenance works.W.e.f.14.08.2018.

Enclosed please find herewith the revised rate list for supply & erection of items/material for estimation purpose of preventive maintenance works w.e.f. 14.08.2018 (the rates are inclusive of all taxes). The letter and rate list issued earlier vide this office memo no. Ch-5/L-433/P&D dated 24.03.2018 be treated as cancelled.

This issue with the approval of WTDs in agenda item No 162.28 placed at Ch-71/ D-III-58/Vol-I

DA/Soft copy of rate list



**Superintending Engineer/P&D,
For C.E/PD&C, DHBVN, Hisar**

CC to:-

1. SPS to CMD, DHBVN, Hisar for information of Worthy CMD, please.
2. PS to Director/Projects, DHBVN, Hisar for information of Director, please.
3. PS to Director/Operation, DHBVN, Hisar for information of Director, please.
4. C.E/MM, DHBVN, Hisar.
5. C.E/PD&C, DHBVN, Hisar.
6. C.E/OP, DHBVN, Hisar/Delhi.
7. CE/Smart City,DHBVN,Hisar.
8. CE/Commercial,DHBVN,Hisar.
9. CE/R-APDRP,DHBVN,Hisar
10. CFO,DHBVN,Hisar.
11. SE/Const.,DHBVN,Hisar.
12. SE/MM,DHBVN,Hisar.
13. S.E/R-APDRP, DHBVN, Hisar
14. COS, DHBVN, Hisar.
15. SE/Civil,DHBVN,Hisar.
16. FA/PD&C, DHBVN, Hisar.
17. FA/MM, DHBVN, Hisar.
18. FA/HQ, DHBVN, Hisar.
19. CDM o/o C.E/PD&C, DHBVN, Hisar.
20. SE/IT, DHBVN, Hisar.

(along with a copy of rate list for information and it is requested to upload the rate list on Nigam Website and confirmation of the same be supplied to this office).

along with copy of rate list for information & necessary action please

Revised rate list for Supply & Erection of the items/material for estimation purpose of preventive maintenance works W.e.f. 14.08.2018.


Sr. No	Description of Material	Unit	Revised Rates for Supply including GST	Revised Rates for Erection including applicable taxes
1	Male contact (for G.O Switch) heavy duty	No.	324	100
2	Female contact (for G.O Switch) heavy duty	No.	324	100
3.	G.I. pipe for GO switch			
3(a)	G.I. Pipe (having free length of 5100 mm, 25 mm inner dia. & 32 mm outer dia., min. weight-10.5 KG) excluding the length of handle	No.	722.20	200
(b)	G.I. Pipe (having free length of 6000 mm 25 mm inner dia. & 32 mm outer dia., Min.weight 12.750 KG) excluding the length of	No.	966	250
4	Handle (for G.O. Switch)	No.	400	100
5	HT Brass Rod	No.	175	175
6	LT Brass Rod For			
i)	25 KVA DT	No.	175	175
ii)	63 KVA DT	No.	175	175
iii)	100 KVA DT	No.	175	175
iv)	200 KVA DT	No.	328	200
v)	400 KVA DT	No.	462.95	300
7	HV Bushing 12 mm	No.	125	125
8	LV Bushing (up to 400 KVA) 12 mm	No.	40	40
	20 mm		40	40
	25 mm		100	100
9	Gasket sheet	No.	740.75	150
10	Breather (up to 100 KVA)	No.	200	25
11	Breather (above 100 KVA)	No.	280	25
12	Silica Gel	Kg.	160.20	10
13	Bimetallic Clamp for HV side	No.	83.35	15
	Clamp for HT Rod (UDC)	No.	55	15
14	Bimetallic Clamp for LV side For			
i)	25 KVA DT	No.	83.35	15
ii)	63 KVA DT	No.	83.35	15
iii)	100 KVA DT	No.	100	15
iv)	200 KVA DT	No.	100	15
v)	400 KVA DT	No.	277.80	15
15	HT Empire Tape Roll 1"/10 Mtr.	No.	15.40	20
	HT Empire Tape Roll 1"/20 Mtr.	No.	27.00	20
16	PVC Tape Roll ¾ "/10 Mtr.	No.	7.40	20

i)	PVC Tape Roll ¾"/6.5 Mtr.	No.	7.30	20
ii)	Black Friction Tape ¾"/17 Mtrs.	No.	7.40	20
iii)	Cotton Tape 1"/25 Mtr	No.	7.40	20
iv)	HT Tape Rubberized (11 KV) 1 1/2"/9.1 Mtr	No.	450	20
17 (i)	Wooden Cleat off sizes	No.	69.45	25
(ii)	Large wooden cleats with 2 holes for 1Cx120 sqmm cable	No.	80	25
18	Charcoal	KG.	18.50	0
19	Salt	KG.	9.25	0
20	J bolt to hold the DT at platform	No.	83.35	25
21	To set right the tilted pole	No.	-	50% of scheduled erection rate
22	To set right the loose sag of HT/LT Line	Mtr.	-	50% of scheduled erection rate if no height raising is required. Otherwise additional Rs. 100/- per pole for raising of height
23	Maintenance of 11 kV GO Switch with replacement of damaged male/female contracts & its alignment complete in all	No.	-	Rs. 550 per GO switch
24	Jumper replacement (D)	No.	-	Rs.100 per jumper
25	Tree Cutting	Per Span	-	Rs. 100 per span
26	Lead replacement (DT to fuse unit)	No.	-	Rs.100 per lead with thimble provision at fuse unit end & DT end with bimetallic clamp
27	Cable provision from fuse unit to LT Pole	No.	-	Rs.500 per DT with thimble at fuse unit end & PG clamp at LT pole
28	Guarding at Road crossing/ as per site requirement	Per span	-	300
29	Sleeves for PVC cables			
	50mm2	Mtr	21.00	10
	95mm2	Mtr	29.00	10
	120mm2	Mtr	29.00	10
	185mm2	Mtr	40.00	10
	300mm2	Mtr	60.00	10
30	C Type Wedge Connectors for ACSR			
	50 mm2	No.	200	Labour included in jumper

	80 mm ²	No.	225	replacement
	100 mm ²	No.	250	
31	All Thimble	No.		
	50mm	No.	7.50	5
	70mm	No.	10	5
	95mm	No.	10	5
	120mm	No.	11.90	5
	150mm	No.	15.00	5
	185mm	No.	19.50	5
	300mm	No.	45.00	5
32	Fuse Wire			
	28SWG (200gm, Reel)	Per reel	58.00	Included in H-Pole
	26SWG (200gm, Reel)	Per reel	57.00	
	30SWG (200 gm, Reel)	Per reel	59.00	
33	PG Clamp			
	2 bolted for 50 sq mm ACSR	No.	35.00	Included in jumper replacement
	3 bolted for 80/100 sq mm ACSR	No.	75.00	
34	PVC Spacers, spiral type			
	2 line	No.	13.00	10
	3 line	No.	20.00	10
	4 line	No.	25.00	10

NOTE: -

1. For items mentioned at sr. no. 5 to 12 in the above list, Rs. 1500/- per transformer for complete overhauling.
2. Rs. 3000/- per H-pole/4-pole pole mounted sub-station for complete overhauling including transformer, GO switch, HT/LT jumpers, HT/LT fuse units, LT cable from fuse unit to common pole and from transformer to LT fuse unit.


Superintending Engineer/P&D
For CE/PD&C, DHBVN Hisar