



DAKSHIN HARYANA BIJLI VITRAN NIGAM

Regd. Office: Vidyut Sadan, Vidyut Nagar, Hisar – 125 005 (Haryana)

Telephone: 01662-223254 (O), 01662-223254 (Fax)

E-mail: xenmon@gmail.com

O/O. DGM Monitoring, DHBVN, Hisar

Instruction No. 57 /MON/2014

To

All GMs (OP),
Under DHBVN.

Memo No. Ch-249/Mon- 260/Vol-VI. Dated: 18/07/2014

Subject: Maintenance of 11 KV feeders.

To save the power transformers from getting damage and to ensure the quality / uninterrupted power supply to the consumers, proper maintenance of power transformers and 11 KV feeders shall be carried out by all the field offices in their area of jurisdiction. The instructions / directions for the same stands already issued vide Instruction No. 47/MON/2010 circulated vide this office memo Ch-85/Mon-260/Vol-I dated 9.8.2010 The matter regarding maintenance of 11KV feeders has been discussed / deliberated in the various meetings and it has been decided that due to weak monsoon, there is unprecedented increase in load/ demand resulting into frequent break down. Large number of power transformers have damaged in DHBVN & HVPN. So to ensure the continuity of supply and to avoid breakdowns, **the maintenance of 1st 2.00 K.Ms length starting from the sub station of each feeder shall be carried out on priority by all the DGMs/ AGMs /OP in their area**, so that travel of heavy current on power transformer could be avoided / controlled. During maintenance at least following activities shall be carried out:


1. The status of earthing of 1st H-Pole of all the feeders under their jurisdiction by taking the values physically along with SSE in case of HVPN sub stations be checked. It shall be ensured that the values are within the norms fixed by the Nigam/REC. In case the earthing of first H-pole yet not stand provided, the same shall be provided now as per instruction of the Nigam by availing the already procured material.
2. The tightening and proper sagging of loose conductor of all the 11 KV feeders shall be carried out. It shall be ensured that the conductor on any feeder is not left loose.
3. Tree cutting on feeder be ensured.
4. Jumper of appropriate size with P.G. clamps on proper binding length be provided.
5. X-arms / top hamper where loose / tilted be set right.

All DGM/AGM (OP) shall complete the maintenance work in 1st 2 KM of all the 11

KV Feeders in their area **within 10 days** and will issue a certificate that the above said all the activities have been carried out on all the feeders under their jurisdiction as per instruction of Nigam and are functioning properly to GM (OP) concerned. Further GMs (OP) shall review & issue the consolidated certificate for their circle **within 15 days** to this office. The CGM/GM (OP) shall monitor the campaign at their level to ensure that above said activities are completed in time and certificate in this regard are issued by all the offices under their jurisdiction.

It shall be ensured that above instructions are complied with meticulously with immediate effect.

This issues with the approval of MD, DHBVN



Coordinator,
DHBVN, Hisar.

Endst.No **Ch-248/Mon-260/Vol- VI**

Dated: 18/07/2014.

Copy of the above is forwarded to the following for information please:-

1. SPS to MD, DHBVNL, Hisar.
2. SPS to Director (OP), DHBVNL, Hisar.
3. PS to Director/Projects, DHBVNL, Hisar
4. CGM/OP, DHBVN, Delhi.
5. CGM/OP, DHBVN, Hisar.
6. CGM/HR&Admn., DHBVNL, Hisar
7. CGM/P&D, DHBVNL, Hisar.
8. CGM/MM, DHBVNL, Hisar.
9. CGM/Commercial, DHBVNL, Hisar.
10. Controller of Finance, DHBVN, Hisar.
11. CGM/Audit, DHBVNL, Hisar.
12. CGM/Accounts, DHBVNL, Hisar.
13. GM/Energy Audit, DHBVNL, Hisar.
14. GM/IT, DHBVNL, Hisar. He is requested to incorporate the same on DHBVNL, Web site for updating the web site.
15. COS, DHBVNL, Hisar.
16. GM/M&P Circle, DHBVNL, Gurgaon.
17. Company Secretary, DHBVNL, Hisar.
18. All DGMs (OP) under DHBVN.
19. DGM/Enforcement, DHBVNL, Hisar/Gurgaon/Faridabad.
20. DGM/M&P, DHBVNL, Hisar/Faridabad/ Bhiwani/Gurgaon
21. DGM/Central Store, DHBVNL, Hisar/ Ballabgarh.


Coordinator,
DHBVN, Hisar.